

# Luffing Jib Raising Procedure

Luffing Jib No. LJ11:680-681-682 on  
Boom No. B65:685-680  
with Mast No. M11:684

MLC650  
VPC-MAX

## Recommended boom and luffing jib raising and lowering procedure

MLC650 VPC-MAX SERIES 1 must be equipped with 440,900 lb VPC (Variable Position Counterweight); MLC650 VPC-MAX SERIES 2 must be equipped with 661,300 lb VPC; MLC650 VPC-MAX SERIES 3 must be equipped with 881,800 lb VPC. Refer to Luffing Jib Rigging **No. 84038308** for boom and luffing jib make-up of inserts, straps, struts, strut raising and lowering procedure, jib stop operation and miscellaneous parts, etc. Refer to the Operator Manual for setup and installation.

**Caution:** Any time luffing jib point rollers are in contact with ground during raising or lowering procedure, release swing brake. *Structural damage can occur.*

**Caution:** Do not under any condition allow boom-to-luffing jib angle to become less than 70 degrees. *Structural damage can occur.*

### Raising:

Starting position for the jib stops is resting on fully retracted jib stop support cylinders. Luff up jib strut until straps on inserts are clear of strap supports. Slowly raise boom while luffing jib point rollers are allowed to roll on ground. Tension should be applied to luffing jib hoist to keep jib straps clear of strap supports. Boom up and luff down until boom-to-luffing jib angle reaches value specified in Tables 1 thru 6 or luffing jib is vertical, whichever occurs first. Tighten luffing jib suspension with luffing jib hoist. Boom and luffing jib are then raised together using boom hoist until boom reaches 85 degrees or the operating radius is within capacity chart and luffing jib is above horizontal. If boom-to-luffing jib angle is greater than 135 degrees, lower luffing jib to obtain this angle to allow jib stops to properly position. Ensure both jib stop positioning rollers have correctly located the jib stops (jib stop support cylinders extended) and are flipped over center towards the boom top with pendants slack.

**Warning:** Failure to lower luffing jib to 135 degree boom-to-luffing jib angle will not allow jib stops to engage. *Structural damage and/or loss of luffing jib stability can occur.*

### Lowering:

Position boom at 85 degrees prior to lowering luffing jib. Lower luffing jib until boom-to-luffing jib angle reaches value specified in Tables 1 thru 6. Lower boom until luffing jib point rollers contact ground. If luffing jib is hanging vertical, raise luffing jib a few degrees forward of vertical. Should luffing jib fail to roll along ground it may be necessary to provide outside assistance. Continue to lower boom while luffing jib rolls along ground until boom to luffing jib angle reaches a maximum of 150 degrees and activate jib stop support cylinder release. Keep enough tension on luffing jib hoist to keep jib straps clear of strap supports.

**Warning:** If luffing jib fails to roll once luffing jib point rollers contact ground, lock counterweight until boom-to-luffing jib angle has reached 135 degrees. Luffing jib point rollers must remain on ground with jib straps slack. Once boom-to-luffing jib angle has reached 135 degrees unlock counterweight and continue booming down. *Failure to lock and unlock counterweight as instructed may result in a loss of machine stability.*

**Warning:** Do not under any condition allow boom-to-luffing jib angle to become greater than 150 degrees before activating jib stop positioning cylinder release. Jib stop may engage boom top during lowering. *Structural damage can occur.*

# Luffing Jib Raising Procedure

Luffing Jib No. LJ11:680-681-682 on  
 Boom No. B65:685-680  
 with Mast No. M11:684

## MLC650 VPC-MAX

Refer to Tables 1 thru 6 for raising ability with the maximum weight of load blocks, hooks, weight balls, slings and hoist lines beneath boom and jib point sheaves. For block weights shown with #, load blocks, hooks, weight balls and slings must remain on ground until combined weights are within rated capacity of chart.

**Table 1**

MLC650 VPC-MAX SERIES 1 38.7 ft Counterweight Position										
Boom Length	Boom to Luffing Jib Angle	Over End of Blocked Crawlers				Over End or Side of Crawlers				Boom to Luffing Jib Angle
		Weight Under Load Point								
		Boom	Jib	Boom	Jib	Boom	Jib	Boom	Jib	
Feet	Degrees	#	#	18,000 lb	21,000 lb	#	#	18,000 lb	21,000 lb	Degrees
183.7	135	85.3 - 95.1	—	—	—	—	—	—	—	135
	90	85.3 - 232.9	—	—	—	85.3 - 173.9	—	—	—	90
	70	85.3 - 331.4	85.3 - 272.3	85.3 - 272.3	—	—	—	—	—	70
203.4	135	—	—	—	—	—	—	—	—	135
	90	85.3 - 105.0	—	—	—	—	—	—	—	90
	70	85.3 - 232.9	—	—	—	—	—	—	—	70

**Warning:** Crane must remain in-line with crawlers when raising over end of blocked crawlers until operating radius and crane configuration is within 360 degree chart. *Crane tipping or structural damage can occur.*

**Table 2**

MLC650 VPC-MAX SERIES 2 38.7 ft Counterweight Position										
Boom Length	Boom to Luffing Jib Angle	Over End of Blocked Crawlers				Over End or Side of Crawlers				Boom to Luffing Jib Angle
		Weight Under Load Point								
		Boom	Jib	Boom	Jib	Boom	Jib	Boom	Jib	
Feet	Degrees	#	#	18,000 lb	21,000 lb	#	#	18,000 lb	21,000 lb	Degrees
183.7	135	85.3 - 193.6	85.3 - 124.7	85.3 - 173.9	85.3 - 95.1	135				
	90	85.3 - 331.4	85.3 - 272.3	85.3 - 311.7	85.3 - 232.9	90				
	70	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	70				
203.4	135	85.3 - 164.0	85.3	85.3 - 124.7	—	135				
	90	85.3 - 292.0	85.3 - 213.3	85.3 - 252.6	85.3 - 124.7	90				
	70	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	70				
223.1	135	85.3 - 105.0	—	—	—	135				
	90	85.3 - 232.9	—	85.3 - 173.9	—	90				
	70	85.3 - 331.4	85.3 - 272.3	85.3 - 272.3	—	70				
242.8	135	—	—	—	—	135				
	90	85.3 - 124.7	—	—	—	90				
	70	85.3 - 272.3	—	—	—	70				

**Warning:** Crane must remain in-line with crawlers when raising over end of blocked crawlers until operating radius and crane configuration is within 360 degree chart. *Crane tipping or structural damage can occur.*

# Luffing Jib Raising Procedure

Luffing Jib No. LJ11:680-681-682 on  
 Boom No. B65:685-680  
 with Mast No. M11:684

**MLC650  
 VPC-MAX**

Table 3

MLC650 VPC-MAX SERIES 3 38.7 ft Counterweight Position										
Boom Length	Boom to Luffing Jib Angle	Over End of Blocked Crawlers				Over End or Side of Crawlers				Boom to Luffing Jib Angle
		Weight Under Load Point								
		Boom #	Jib #	18,000 lb	21,000 lb	Boom #	Jib #	18,000 lb	21,000 lb	
Feet	Degrees	Luffing Jib Length - Feet								Degrees
183.7	135	85.3 - 272.3		85.3 - 213.3		85.3 - 232.9		85.3 - 173.9		135
	90	85.3 - 331.4		85.3 - 272.3		85.3 - 331.4		85.3 - 272.3		90
	70	85.3 - 331.4		85.3 - 272.3		85.3 - 331.4		85.3 - 272.3		70
203.4	135	85.3 - 232.9		85.3 - 173.9		85.3 - 213.3		85.3 - 134.5		135
	90	85.3 - 331.4		85.3 - 272.3		85.3 - 331.4		85.3 - 272.3		90
	70	85.3 - 331.4		85.3 - 272.3		85.3 - 331.4		85.3 - 272.3		70
223.1	135	85.3 - 193.6		85.3 - 124.7		85.3 - 164.0		85.3		135
	90	85.3 - 331.4		85.3 - 272.3		85.3 - 331.4		85.3 - 213.3		90
	70	85.3 - 331.4		85.3 - 272.3		85.3 - 331.4		85.3 - 272.3		70
242.8	135	85.3 - 164.0		—		85.3 - 124.7		—		135
	90	85.3 - 311.7		85.3 - 173.9		85.3 - 272.3		—		90
	70	85.3 - 331.4		85.3 - 272.3		85.3 - 331.4		85.3 - 272.3		70
262.5	135	85.3 - 114.8		—		—		—		135
	90	85.3 - 252.6		—		85.3 - 164.0		—		90
	70	85.3 - 331.4		—		85.3 - 272.3		—		70
282.2	135	—		—		—		—		135
	90	85.3 - 134.5		—		—		—		90
	70	85.3 - 272.3		—		—		—		70

**Warning:** Crane must remain in-line with crawlers when raising over end of blocked crawlers until operating radius and crane configuration is within 360 degree chart. *Crane tipping or structural damage can occur.*

# Luffing Jib Raising Procedure

Luffing Jib No. LJ11:680-681-682 on  
 Boom No. B65:685-680  
 with Mast No. M11:684

## MLC650 VPC-MAX

Table 4

MLC650 VPC-MAX SERIES 1 60.0 ft Counterweight Position										
Boom Length	Boom to Luffing Jib Angle	Over End of Blocked Crawlers				Over End or Side of Crawlers				Boom to Luffing Jib Angle
		Weight Under Load Point								
		Boom #	Jib #	18,000 lb	21,000 lb	Boom #	Jib #	18,000 lb	21,000 lb	
Feet	Degrees	Luffing Jib Length - Feet								Degrees
183.7	135	85.3 - 193.6	85.3 - 124.7	85.3 - 164.0	85.3	135				
	90	85.3 - 331.4	85.3 - 272.3	85.3 - 292.0	85.3 - 213.3	90				
	70	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	70				
203.4	135	85.3 - 144.4	—	85.3 - 124.7	—	135				
	90	85.3 - 272.3	85.3 - 193.6	85.3 - 252.6	85.3 - 95.1	90				
	70	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	70				
223.1	135	85.3 - 95.1	—	—	—	135				
	90	85.3 - 213.3	—	85.3 - 144.4	—	90				
	70	85.3 - 331.4	—	85.3 - 272.3	—	70				
242.8	135	—	—	—	—	135				
	90	85.3	—	—	—	90				
	70	85.3 - 232.9	—	—	—	70				

**Warning:** Crane must remain in-line with crawlers when raising over end of blocked crawlers until operating radius and crane configuration is within 360 degree chart. *Crane tipping or structural damage can occur.*

# Luffing Jib Raising Procedure

Luffing Jib No. LJ11:680-681-682 on  
 Boom No. B65:685-680  
 with Mast No. M11:684

## MLC650 VPC-MAX

Table 5

MLC650 VPC-MAX SERIES 2 60.0 ft Counterweight Position										
Boom Length	Boom to Luffing Jib Angle	Over End of Blocked Crawlers				Over End or Side of Crawlers				Boom to Luffing Jib Angle
		Weight Under Load Point								
		Boom #	Jib #	Boom 18,000 lb	Jib 21,000 lb	Boom #	Jib #	Boom 18,000 lb	Jib 21,000 lb	
Feet	Degrees	Luffing Jib Length - Feet								Degrees
183.7	135	85.3 - 292.0		85.3 - 232.9		85.3 - 272.3		85.3 - 213.3		135
	90	85.3 - 331.4		85.3 - 272.3		85.3 - 331.4		85.3 - 272.3		90
	70	85.3 - 331.4		85.3 - 272.3		85.3 - 331.4		85.3 - 272.3		70
203.4	135	85.3 - 272.3		85.3 - 193.6		85.3 - 232.9		85.3 - 164.0		135
	90	85.3 - 331.4		85.3 - 272.3		85.3 - 331.4		85.3 - 272.3		90
	70	85.3 - 331.4		85.3 - 272.3		85.3 - 331.4		85.3 - 272.3		70
223.1	135	85.3 - 213.3		85.3 - 144.4		85.3 - 193.6		85.3 - 124.7		135
	90	85.3 - 331.4		85.3 - 272.3		85.3 - 331.4		85.3 - 272.3		90
	70	85.3 - 331.4		85.3 - 272.3		85.3 - 331.4		85.3 - 272.3		70
242.8	135	85.3 - 173.9		85.3 - 105.0		85.3 - 154.2		—		135
	90	85.3 - 331.4		85.3 - 232.9		85.3 - 311.7		85.3 - 173.9		90
	70	85.3 - 331.4		85.3 - 272.3		85.3 - 331.4		85.3 - 272.3		70
262.5	135	85.3 - 144.4		—		85.3 - 105.0		—		135
	90	85.3 - 272.3		85.3 - 124.7		85.3 - 232.9		—		90
	70	85.3 - 331.4		85.3 - 272.3		85.3 - 331.4		—		70
282.2	135	85.3 - 95.1		—		—		—		135
	90	85.3 - 193.6		—		85.3 - 105.0		—		90
	70	85.3 - 331.4		—		85.3 - 272.3		—		70
301.8	135	—		—		—		—		135
	90	—		—		—		—		90
	70	85.3		—		—		—		70

**Warning:** Crane must remain in-line with crawlers when raising over end of blocked crawlers until operating radius and crane configuration is within 360 degree chart. *Crane tipping or structural damage can occur.*

# Luffing Jib Raising Procedure

Luffing Jib No. LJ11:680-681-682 on  
 Boom No. B65:685-680  
 with Mast No. M11:684

## MLC650 VPC-MAX

Table 6

MLC650 VPC-MAX SERIES 3 60.0 ft Counterweight Position										
Boom Length	Boom to Luffing Jib Angle	Over End of Blocked Crawlers				Over End or Side of Crawlers				Boom to Luffing Jib Angle
		Weight Under Load Point								
		Boom #	Jib #	18,000 lb	21,000 lb	Boom #	Jib #	18,000 lb	21,000 lb	
Feet	Degrees	Luffing Jib Length - Feet								Degrees
183.7	135	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	135
	90	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	90
	70	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	70
203.4	135	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 252.6	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	135
	90	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	90
	70	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	70
223.1	135	85.3 - 311.7	85.3 - 252.6	85.3 - 272.3	85.3 - 213.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	135
	90	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	90
	70	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	70
242.8	135	85.3 - 272.3	85.3 - 213.3	85.3 - 252.6	85.3 - 173.9	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	135
	90	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	90
	70	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	70
262.5	135	85.3 - 232.9	85.3 - 173.9	85.3 - 213.3	85.3 - 144.4	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	135
	90	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	90
	70	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	70
282.2	135	85.3 - 213.3	85.3 - 124.7	85.3 - 173.9	85.3 - 95.1	85.3 - 331.4	85.3 - 213.3	85.3 - 331.4	85.3 - 272.3	135
	90	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 213.3	85.3 - 331.4	85.3 - 213.3	85.3 - 331.4	85.3 - 272.3	90
	70	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	70
301.8	135	85.3 - 164.0	85.3	85.3 - 134.5	—	85.3 - 331.4	85.3 - 134.5	85.3 - 331.4	85.3 - 272.3	135
	90	85.3 - 331.4	85.3 - 173.9	85.3 - 272.3	—	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	90
	70	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	85.3 - 331.4	85.3 - 272.3	70
321.5	135	85.3 - 124.7	—	85.3	—	85.3 - 331.4	85.3	85.3 - 331.4	—	135
	90	85.3 - 232.9	—	85.3 - 164.0	—	85.3 - 331.4	85.3 - 164.0	85.3 - 331.4	—	90
	70	85.3 - 331.4	—	85.3 - 311.7	—	85.3 - 331.4	85.3 - 311.7	85.3 - 331.4	—	70
341.2	135	—	—	—	—	85.3 - 331.4	—	85.3 - 331.4	—	135
	90	85.3 - 134.5	—	—	—	85.3 - 331.4	—	85.3 - 331.4	—	90
	70	85.3 - 272.3	—	—	—	85.3 - 331.4	—	85.3 - 331.4	—	70

**Warning:** Crane must remain in-line with crawlers when raising over end of blocked crawlers until operating radius and crane configuration is within 360 degree chart. *Crane tipping or structural damage can occur.*